



# FORTTRUST®

THE RECOGNIZED LEADER IN  
DATA CENTER COLOCATION SERVICES



## FORTTRUST DENVER DATA CENTER SPECIFICATIONS

- » 300,000 square feet of data center facility
- » Tier III Certification of Constructed Facility from the Uptime Institute
- » Modular “plug and play” infrastructure throughout the critical system’s design allows for expansion without interruption
- » Extensive risk mitigation features and attributes
- » 50,000 square feet of operational raised-floor space and 65,000 square feet of data modules all on ground floor/slab
- » Facility located outside the 100 and 500 year flood plains

## COLOCATION (RAISED FLOOR AND DATA MODULES)

- » Cabinets, cages, and data modules ranging from 100 square feet and above
- » 100 and 200kW @ 2N data modules
- » Densities up to 35kW/rack in data modules
- » Individual data module PUEs’ of <1.2

## POWER

- » 34 MW of data center infrastructure
- » 2N (“A” & “B” side) electrical distribution to critical loads
- » Multiple 1,000kVA and 750kVA uninterrupted power supply (UPS) systems in a 2N+1 configuration
- » 2MW and 2.5MW generators in an N+1 configuration

## COOLING

- » Closed-loop chilled water system; chillers, pumps and computer room air handling units
- » Dual path and bi-directional distribution
- » 36 inch raised floor for optimum cooling
- » High density cooling in data modules >1000 watt/sq.ft. or 35kW/rack

## ACCESS & CONNECTIVITY

- » Carrier and cloud neutral facility
- » Secure diverse vaulted underground entrances
- » Multiple carrier fiber facilities and WAN connectivity options

## OPERATIONS & SECURITY

- » Tier III GOLD Certification of Operational Sustainability
- » 7X24 on-site operations and customer support
- » 7X24 on-site security guards
- » Multiple layers and types of two factor authentication and access control; including biometric, motion-sensor activated cameras and digital recording
- » Additional off-site 3rd party security monitoring
- » COLOVIEW® Service via extensive DCIM system

## SERVICES

- » 7X24 equipment receiving services
- » 7X24 remote hands with 30 minute SLA
- » High-availability Managed Internet Access (MIA) service (house/blended bandwidth)
- » Rack and stack services
- » Multiple customer drop-in, test and turn-up areas
- » Onsite conference and office space

## CUSTOMER SERVICE/SUPPORT

- » 7X24 customer service with a “sense of urgency”
- » Reach a live person 7X24 via email or phone; no call centers or automated “queue” ticketing systems
- » 100% customer satisfaction ratings as surveyed year after year

## COMPLIANCE

- » SSAE 16 Service Organization Control (“SOC”) 1 Type II
- » SOC 2 Type II
- » SOC 3 SysTrust Services Organization
- » PCI/DSS (sections 9 &12)
- » BBB A+ Accreditation
- » HIPAA
- » GLBA

